अखिल भारतीय आयुर्विज्ञान संस्थान, गोरखपुर
All India Institute of Medical Sciences, Gorakhpur
कुनराघाट गोरखपुर उत्तर प्रदेश - 273008
Kunraghat, Gorakhpur, Uttar Pradesh 273008
(स्वास्थ्य एवं परिवार कल्याण मंत्रालय, भारत सरकार द्वारा स्थापित एक स्वायत्त निकाय)
(An autonomous organization under the Ministry of Health & Family Welfare, Govt. of India)

Comp- 7048

Ref No. AIIMS/GKP/EW/ 2026-27/709 Date :05/11/2026

Quotation Notice

Quotations are invited from intending registered Stockist/Distributors/ Suppliers/ OEMs having GST and relevant documents for repair boundary wall of the institute as directed by engineer incharge (all material to be branded) (**annexure attached**) at AIIMS. The quotation should be dropped in the Quotation Box located at Ground Floor of Administrative Block, Medical College Building, AIIMS, Gorakhpur, U.P. latest by 13 Nov, 2026 till 4:00 pm. Any quotation received through e-mail or after the last date will not be entertained. Details of material

Terms & Condition

Prices should be clearly mentioned in the offer.

- The sealed envelope should bear quotations number and the subject of quotation (Eng. Department).
- Supply & installation should be completed within 30 days from the date of purchase order.
- Price should be inclusive of GST.
- Contact number with address and email id should be mentioned in the quotation.
- Order will be placed to the L-1 vendor on total value basis.
- Validity of the quotation should be 30 days from the date of opening and validity.
- Validity period for rates should be clearly mentioned in the quotation.
- Firm to submit documentary evidence in support of claim of GST at the time of submission of bills.
- Sample may be asked for evaluation before/after final placement of order.

Following quotations will be summarily rejected:

01.Quotations not received in sealed envelope.
02. Quotations without quotation enquiry number.
03.Quotations received without mentioning of Subject at the top of envelope.
04Quotations received without mentioning of Name of the firm on envelope.
05Quotations without GSTIN Number.
06.Quotations received without mentioning of address & email-ID of the firm
07. Quotations received without mentioning date of validity

For any clarifications, kindly contact at email address: se@aiimsgorakhpur.edu.in.

LT Col Manish Kumar / Supdt. Engr. (EW) 5/11/2026

अखिल भारतीय आयुर्विज्ञान संस्थान, गोरखपुर
All India Institute of Medical Sciences, Gorakhpur
कुनराघाट गोरखपुर उत्तर प्रदेश - 273008
Kunraghat, Gorakhpur, Uttar Pradesh 273008
(स्वास्थ्य एवं परिवार कल्याण मंत्रालय, भारत सरकार द्वारा स्थापित एक स्वायत्त निकाय)
(An autonomous organization under the Ministry of Health & Family Welfare, Govt. of India)

Gap filling of Boundry Wall Work						
S.No	Ref DSR 2023	Description	UOM	Qty	Rate/Unit Incl. GST	Amount Incl. GST
		AIRPORT ROAD SIDE NEAR UNDER PASS				
1	2.38	Filling with available fly ash and earth (excluding rock) in trenches or embankment in layers (each layer should not exceed 15 cm), with intermediate layer of compacted earth (Soil density of 98%) after every four layers of compacted depth of fly ash, sides & top layer of filling shall be done with earth having total minimum compacted thickness 30 cm or as decided by Engineer -in-charge, including compacting each layer by rolling/ ramming and watering, all complete as per drawing and direction of Engineer -in - charge	cum	10		
		GATE NO 1 & 2 GAP B/W WALL AND GATE				
1	6.4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :	CUM	1.5		
	6.4.2	Cement mortar 1:6 (1 cement : 6 coarse sand)				
2	13.19	Rough cast plaster upto 10 m height above ground level with a mixture of sand and gravel or crushed stone from 6 mm to 10 mm nominal size, dashed over and including the fresh plaster in two layers, under layer 12 mm cement plaster 1:4 (1 cement : 4 coarse sand) and top layer 10 mm cement plaster 1:3 (1 cement : 3 fine sand) mixed with 10% finely grounded hydrated lime by volume of cement.	sqm	9		
	13.19.1	Ordinary cement finish using				

Lt Col Manisha Tiwari / लेफ्टिनेंट कर्नल मनीषा तिवारी
Superintending Engineer / अधीक्षण अभियंता
Department / विभाग
All India Institute of Medical Sciences / अखिल भारतीय आयुर्विज्ञान संस्थान
Gorakhpur-273008 / गोरखपुर-273008
5/11/26

3	13.46	Finishing walls with Acrylic Smooth exterior paint of required shade :	sqm	9		
	13.46.1	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)				
		AIRPORT ROAD SIDE NEAR GATE NO 1				
1	6.4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :	CUM	1.5		
	6.4.2	Cement mortar 1:6 (1 cement : 6 coarse sand)				
2	13.19	Rough cast plaster upto 10 m height above ground level with a mixture of sand and gravel or crushed stone from 6 mm to 10 mm nominal size, dashed over and including the fresh plaster in two layers, under layer 12 mm cement plaster 1:4 (1 cement : 4 coarse sand) and top layer 10 mm cement plaster 1:3 (1 cement : 3 fine sand) mixed with 10% finely grounded hydrated lime by volume of cement.	sqm	10		
	13.19.1	Ordinary cement finish using ordinary cement				
3	13.46	Finishing walls with Acrylic Smooth exterior paint of required shade :	sqm	10		
	13.46.1	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)				
		BOUNDARY WALL ALONG THE AIRPORT ROAD SIDE CONSISTS OF IRON GRILL WITH GAPS				
1	16.7	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of	sqm	20		

LT Col Manisha Tiwari / लेफ्टिनेंट कर्नल मनीषा तिवारी
Superintending Engineer / अधीक्षण अभियंता
Department / विभाग
Address / पता
अखिल भारतीय आयुर्विज्ञान संस्थान गोरखपुर-273008
5/11/26

		Engineer-in-charge. Made of G.I. wire of dia 4 mm				
	GATE NO. 1,2,3 &4 OPEN GRILL SECTION AND BOLLTOM CLEARANCE					
1	16.7	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia 4 mm	sqm	32		

LT [illegible]nisha Tiwari / लेफ्टिनेंट कर्नल मनीषा तिवा
Superintendent Engineer / अधीक्षक अभियंत
Department of Engineering / इंजीनियरिंग विभ
All India Institute of Medical Sciences, Gorakhpur-2730
अखिल भारतीय आयुर्विज्ञान संस्थान, गोरखपुर-2730